BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT48285

NAME OF WORK: Maintainace and repairs of UGD and desilting of drains in silt and tractors in ward no 12 shettyhalli Shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri G VENKATESH (MAHENDRA ENGINEERING WORKS)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	2084.42	199.0	Rupees One Hundred Ninety Nine Only
2	Providing and laying in position to required level or slope 230mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Mtr	1028.00	596.0	Rupees Five Hundred Ninety Six Only
3	Providing and laying in position plain cement concrete M7.5 40mm and down size graded granite metal, machine mixed concrete laid in layers not exceeding 15 cms thick, well compacted, for 230mm internal diameter stoneware pipes including cost of materials, labour charges, HOM of machinery, curing complete as per the specification & as per direction of Engineer-in-charge of the work	Mtr	1028.00	544.0	Rupees Five Hundred Forty Four Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division.

Scanned with Oken Scanner

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri G VENKATESH (MAHENDRA ENGINEERING WORKS)	
				In Figures (Rs.)	In Words (Rs.)
4	Constructing brick masonry circular type manhole 0.91m internal dia at bottom,1.67m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diametre confirming IS :12592, total weight cover and frame to be not less than 182 kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid seperately) complete as per the specification & as per direction of Engineer-in-charge of the work	Nos	10.00	27015.0	Rupees Twenty Seven Thousand Fifteen Only
5	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per the specification & as per direction of Engineer-in-charge of the work	Cum	2084.42	135.0	Rupees One Hundred Thirty Five Only
6	Supply of the 50 HP Tractor on daily rate basis to the required place complete as per the specification & as per direction of Engineer-in-charge of the work	Nos	552.00	1352.0	Rupees One Thousand Three Hundred Fifty Two Only
7	Supply of the Labour Heavy Mazdoor to the required place complete as per the specification & as per direction of Engineer-in-charge of the work	Month	2760.00	468.0	Rupees Four Hundred Sixty Eight Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Scanned with Oken Scanner

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri G VENKATESH (MAHENDRA ENGINEERING WORKS)	
				In Figures (Rs.)	In Words (Rs.)
8	J.C.B. Excavator on hire basis including JCB Operator with Helper to carryout the works on emergency complete as per the specification & as per direction of Engineer-in-charge of the work	Nos	120.00	5990.0	Rupees Five Thousand Nine Hundred Ninety Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Scanned with Oken Scanner